

KANSAS

*SP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sohio Petroleum Company

Complete Address Box 673 Russell, Kansas 67665

Lease Name Frevele "B" Well No. 1

Location C NE NE Sec. 27 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4535'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:15 A Day 29 Month 9 Year 1972

The above well was plugged as follows:

Total Depth 4535' 10 3/4 csg set at 297' cwc:

7" csg set at 4510' cw 175 sk cmt.

Filled 7" csg W/sd (4500-4535) Dumped 6 sk cmt W/dump bailer. (4465-4500)

Cutoff and recovered 1192" of 7" csg.

Pumped down 10 3/4 csg with 45 sk gek & water W/500 lbs hulls at 900 lbs pres.

Released 10 3/4 plug and pumped 150 sk "Halco-light" cmt. 300 lbs PP 200 lbs SIP

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE: 10-2-72

INV. NO. 6398-42