

15.B5.20187-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*RP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name Conkright Well No. 1

Location SW NW Sec. 27 Twp. 16 Rge. 25 (E)    (W) X

County Ness Total Depth 4520'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A XX

Other well as hereafter indicated:   

Plugging Contractor: Co. Tools

Address:    License No.   

Operation Completed: Hour 3:30A Day 27 Month 9 Year 1968

The Above well was plugged as follows:

RTD 4520' 8 5/8 csg set at 309' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 - 1968

CONSERVATION DIVISION  
Wichita, Kansas

Signed: Geo F. Murray  
Well Plugging Supervisor

NOTICED

DATE 10/1/68  
INV. NO. 8548-W