

15-135-00121-00-00

R

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 117-41 County: Ness

Location: ne ne SW Sec. 27 Twp. 16 Rge. 25 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 4508

I have this date completed supervision of plugging of:

Lease Name: Burrell # Well No. 1

Operator's Full Name: Leo J Dreiling

Complete Address: Victoria, Kansas

Plugging Contractor: Ace Pipe Pulling

Address: Box 304 Great Bend Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9am Day 5 Month Aug Year 1958

The above well was plugged as follows:

TD-4508 8-5/8" set at 284' 5 1/2" set at 4490'

Sand to 4990' and 5 sax cement, shot and broke pipe at 3800' and pulled

pipe to 600'. Cir. hole with 40 sax mud and displaced 20 sax cement thru

5 1/2" casing, pulled pipe to 260' heavy mud and displaced 20 sax cement thru

5 1/2" casing, pulled pipe out of hole, heavy mud to 40', built solid rock

bridge and topped with 10 sax cement to bottom of cellar.

Mud and cementing by Sun Cementing Co.

Gilbert P. Leiker

Signed: Gilbert P. Leiker  
Conservation Division Agent

Reviewed: J Lewis Brock  
Field Supervisor

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 27 T. 16 R. 25W  
BOOK PAGE 117 LINE 41