

15-135-00480-00-00

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name J. M. Huber Corporation

Complete Address P. O. Box 911 Amarillo, Texas 79105

Lease Name Burrell Well No. 1

Location C SW SW Sec. 27 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4550'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Culling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12 PM Day 1 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4550' 8 5/8 csg set at 316' owo 300 sk.

4 1/2 csg set at 4550' ow 150 sk cmt.

4 1/2 csg perf. (4481-4502)

Filled 4 1/2 csg w/sd (4465-4550) Dumped 4 sk cmt w/dump bailer. (4430-4465)

Cutoff and recovered 2500' of 4 1/2 csg.

Pumped down 8 5/8 csg with 200 lbs hulls, 20 sk gel & water, 100 lbs hulls, 70 sk

50-50 poz cmt 6%, 12 sk gel & water, released 8 5/8 plug and pumped 50 sk 50-50 poz

cmt 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo G. Massey
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5815-W