

15-101-19017-00-00

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Helmerich & Payne, Incorporated,
 Complete Address: Box #588, Garden City, Kansas.
 Lease Name Leighton Well No. B-1
 Location CNW-NW Sec. 3 Twp. 17 Rge. (E) (W) 27
 County Lane Total Depth 4560
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated:
 Plugging Contractor: Sierra Petroleum Incorporated,
 Address: 208 Petroleum Building, Wichita, Kansas. License No.
 Operation Completed: Hour 5:00AM Day 10 Month 10 Year 1963

The Above well was plugged as follows:

290'--8 5/8" Surface pipe, cement circulated w/200 Sx.
Circulated hole with heavy mud, set plug @ 660' and displaced 20 Sx
cement thru DP. Heavy mud to 285', set plug with 1/2 sk hulls and dis-
placed 20 Sx cement thru DP. Heavy mud to 40', set plug with 1/2 Sk hulls
and 10 Sx cement to bottom of cellar.
(Cementing operations performed by Halliburton Oil Well Cementing Co)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. DeLoach
Well Plugging Supervisor

DATE 10/14/63
INV. NO. 7894-W