

15-101-20058-00-00

Form CP-3
Rev. 6-4-68

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,
Complete Address 408 One-Twenty Building, Wichita, Kansas.
Lease Name Bowles Well No. B-1
Location SE-SE-NW Sec. 3 Twp. 17 Rge. (E) (W) 27
County Lane Total Depth 4549'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Slawson Drilling Company, Incorporated,
Address Above License No.
Operation Completed: Hour 7:15 AM Day 28 Month 4 Year 1973

The above well was plugged as follows:

274'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru DP
from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DA... 4/30/73
INV. NO. 7304-U