

15-101-20012-00-00

Form CP-3
Rev. 6-4-68

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling & Petroleum Resources,
Complete Address Box #18407, Wichita, Kansas.
Lease Name Hagans Well No. H-1
Location T1N-11E-11E Sec. 2 Twp. 17 Rge. (E) (W) 27
County Lane Total Depth 4580'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dunne-Gardner Petroleum, Incorporated,
Address 200 W. Douglas, Wichita, Kansas. License No.
Operation Completed: Hour 7:45 AM Day 8 Month 7 Year 1971

The above well was plugged as follows:

320'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section 0 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge 0 40' with 3 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well Plugging Supervisor

7-14-71
3998-W