

15-101-20009-00-00

Form CP-3
Rev. 6-4-68

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
CORPORATION COMMISSION

MAY 7 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling and Petroleum Resources,
 Complete Address Box#18407, Wichita, Kansas.
 Lease Name Hagans Well No. J-1
 Location NE-NE-SE Sec. 1 Twp. 17 Rge. (E) (W) 27
 County Lane Total Depth 4545'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Dunne-Gardner Petroleum, Incorporated.
 Address 200 West Douglas, Suite 500, Wichita, Kans. License No.
 Operation Completed: Hour 1:00 PM Day 29 Month 4 Year 1971

The above well was plugged as follows:

281'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 500'.
Circulated hole with heavy mud. Pulled DP to 720' and displaced 100 Sx. cement thru
DP from 720' to 400'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
720' 270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/13/71
INV. NO. 3678-11