

15-101-20014-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C & G Drilling Company,

Complete Address 1107 Union National Bank Building, Wichita, Kansas.

Lease Name Ummel Well No. 1

Location SE-NE-NW Sec. 1 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 4285

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 3:00 PM Day 22 Month 7 Year 1971

The above well was plugged as follows:

279'--8 5/8" Surface casing, cement circulated with 150 Sx.
top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru
DP from 875' to 550'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set btidge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dechale
Well Plugging Supervisor

INVOICED

DATE 7-29-71
INV. NO. 4065-W