

15-101-20011-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling and Beacon Resources,
 Complete Address Box #18407, Wichita, Kansas.
 Lease Name Hagans Well No. G-2
 Location SE NW NE Sec. 1 Twp. 17 Rge. (E) (W) 27
 County Tane Total Depth 4588'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Dunne-Gardner Petroleum, Incorporated,
 Address 200 West Douglas, Wichita, Kansas License No.
 Operation Completed: Hour 7:00 AM Day 13 Month 5 Year 1971

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru DP
from 950' to 625'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from 310' to
235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 5/17/71WPAV. NO. 3709-W