

15-101-20037-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum Corporation.

Complete Address Suite 330, Page Court, Wichita, Kansas.

Lease Name Schmieg Estate Well No. 1

Location CNW-NW Sec. 6 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 1665'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated.

Address 475 Page Court, Wichita, Kansas. License No.

Operation Completed: Hour 8:00 AM Day 27 Month 6 Year 1972

The above well was plugged as follows:

285'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/30/72
INV. NO. 5964-W