

15-101-20072-00-00
↑

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company
Complete Address 415 Page Court, Wichita, Kansas.
Lease Name Hineman Well No. 1
Location CSW-NE Sec. 33 Twp. 18 Rge. (E) (W) 28
County Lane Total Depth 4635'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Rains & Williamson Oil Company, Incorporated,
Address 435 Page Court, Wichita, Kansas. License No.
Operation Completed: Hour 8:30 PM Day 23 Month 10 Year 1973

The above well was plugged as follows:

24 1/2" -- 8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/30/73
INV. NO. 8077-10

Signed: W. L. Nichols

Well Plugging Supervisor