

15-101-20132-00-00  
KANSAS Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Incorporated,  
Complete Address 801 Union Center, Wichita, Kansas.  
Lease Name Seifried Well No. 2  
Location CN/2-NW-NW Sec. 25 Twp. 18 Rge. (E) (W) 28  
County Lane Total Depth 4270  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Abercrombie Drilling, Incorporated,  
Address Above License No.       
Operation Completed: Hour 6:00 AM Day 6 Month 12 Year 1974

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 625'.  
Circulated hole with heavy mud. Pulled DP to 850' and displaced 110 Cu. Ft. cement  
thru DP from 850' to 525'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE: 12/13/74  
INV: 454-W