

KANSAS

15-101-20116-00-00

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson
Complete Address 408 One Twenty Bldg., Wichita, Kansas
Lease Name Selfridge "T" Well No. 1
Location NW NW SW Sec. 12 Twp. 18 Rge. (E) (W) 28
County Lane Total Depth 4641'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 11 A Day 20 Month 8 Year 1974

The above well was plugged as follows:

RTD 4641' 8 5/8 csg set at 287' owo 200 sk. Cmt. Mat. 50-50 poz 6% total gol.
Gunned pits, circulated heavy mud, set cementing plug at 950' and displaced
70 sk cmt thru drill pipe. Heavy mud to 240' & displaced 20 sk cmt thru drill
pipe. Heavy mud to 40' set solid bridge & filled to base of cellar with 10 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

8/22/74
9757-W