

15-135-20525-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thornton E. Anderson

Complete Address 710 Union Natl. Bldg., Wichita, Kansas

Lease Name Lamer-Elmore Well No. 1

Location S/2 NE SW Sec. 26 Twp. 17 Rge. (E) (W) 22

County Ness Total Depth 4290'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Woodman & Lannitti Drlg.

Plugging Contractor Wichita, Kansas

Address _____ License No. _____

Operation Completed: Hour 2:30 P Day 5 Month 12 Year 1971

The above well was plugged as follows:

RTD 4290' 8 5/8 csg set at 241' cwc 175 sk Cmt. Mat. 50-50 poz W/4 added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE

12/7/71

INV. NO.

4782-10