

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

2530'

Operator's Full Name Nadel & Gussman

Complete Address: Box 14 Great Bend, Kansas 67530

Lease Name Myer Well No. 1

Location C SW ^{NW} SW ANBCC Sec. 12 Twp. 17 Rge. 22 (E) (W) X

County Ness Total Depth 4388'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399'

Operation Completed: Hour 11:30 Day 7 Month 10 Year 1968

The Above well was plugged as follows:

Total Depth 4388' 8 5/8 csg set at 3223' cw 165 sc.

5 1/2 csg set at 4380' cw 100 sc cement.

5 1/2 csg FBTD 4356' Perf. (4299-4301)

Filled 5 1/2 csg with sand (4275-4356) dumped 5 sc cmt with dump bailer (4275-4235)

Cutoff and recov. 2530' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 24 sc gel & water, W/5 sc hulls, 120 sc 50-50

poz cement W/6% total gel., 6 sc gel & water, plug and 10 sc cement. Max. Pres. 300 lbs

SI pres. 150 lbs. Gmt. (0-40) gal (10-300) Gmt. 300-800 Gal (800-TD)

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION Signed: Geo F. Mansel

Well Plugging Supervisor

OCT 9 - 1968

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE: 10/9/68

INV. NO. 8594-W