


KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Rudy Herman

Complete Address: Box 348 Russell, Kansas

Lease Name ~~Kiewens~~ KIEWENO Well No. 1

Location APP C SE NW Sec. 13 Twp. 17 Rge. 22 (E) (W) X

County Ness Total Depth 4295

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.,

Address: Box 562 Great Bend, Kansas License No. 574

Operation Completed: Hour 4 P Day 27 Month 2 Year 1967

The Above well was plugged as follows:

Total Depth 4295' 8 5/8 csg set at 308 cwc.

5 1/2 csg set at 4288' cw 75 sc cement.

Sand back to 4275' and dumped 5 sc cement with dump bailer.

Recov. 2000' of 5 1/2 csg.

650' Circ. 45 bbl. gel mud thru 5 1/2 csg.

560' Displaced 30 sc. cem. thru 5 1/2 csg.

290' Displaced 25 sc cem. thru 5 1/2 csg.

55' set 10' rock bridge and 15 sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 3/2/67

INV. NO. 4847-W