

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jack Shear Oil Field Supplies

Complete Address: 6320 Jacquelin Wichita, Kansas

Lease Name Kleweno Well No. 1

Location CSE NW Sec. 13 Twp. 17 Rge. (E) (W) 22

County Ness Total Depth 4385

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 5PM Day 16 Month 10 Year 64

The Above well was plugged as follows:

8 5/8" 270' circulated with cement - 5 1/2" 4360' with 100 sax cement.
Perf. at 4289'

Filled with sand to 4260', set 4 sax cement with dump bailer - pulled
3530' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2" at 600'
(20 sax Gel) displaced 20 sax cement through 5 1/2" at 600', heavy mud to
200' displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set
bridge and cemented to bottom cellar.

Mudding and cementing by Forbes Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Petty
Well Plugging Supervisor

10/19/64
1-4