

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
MAY 29 1991
05-29-1991
CONSERVATION DIV
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-101-21,580,000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Ware WELL NO. #5 WELL LOCATION N/2 NE NE COUNTY Lane

SEC. 26 TWP. 19S RGE. 28 (E) or (W) TOTAL DEPTH 4510' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 260.29' CEMENTED WITH 60-40 posmix/180 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, set 1st plug @ 2140' w/50 sx; 2nd plug @ 1300 w/80

sx; 3rd plug @ 1180' w/40 sx; 4th plug @ 300' w/40 sx; 5th plug @ 40' w/10 sx; rathole 15 sx; Total 235 sx

60-40 posmix, 6% gel 1/2# Floseal per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9:00 a.m. 4-19-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE # (913) 743-5443

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 5-28-91

FORM MUST BE SIGNED
FORM C-1 4/90

EFFECTIVE DATE: 4-9-91

State of Kansas

NOTICE OF INTENTION TO DRILL 01-21,580-00-00

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 4 14 91
month day year

N/2 NE NE Sec 26 Twp 19 S, Rg 28 East West

OPERATOR: License # 5393
Name: A. L. Abercrombie, Inc.
Address: 150 N. Main, Suite 801
City/State/Zip: Wichita, KS 67202
Contact Person: Jerry A. Langrehr
Phone: 316-262-1841

4950' feet from South line of Section
660' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

County: Lane
Lease Name: Ware Well #: 5
Field Name: Wildcat
Is this a Prorated Field? yes no
Target Formation(s): Lansing/Kansas City
Nearest lease or unit boundary: 330'
Ground Surface Elevation: APPROX. 2750 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 50-75'
Depth to bottom of usable water: 200-1125'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required: 0
Projected Total Depth: 4400'
Formation at Total Depth: Kansas City
Water Source for Drilling Operations: well farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWD Disposal Wildcat Cable
 Seismic; # of Holes

If OWD: old well information as follows:
Operator: N/A
Well Name: N/A
Comp. Date: N/A Old Total Depth: N/A

DWR Permit #: Will file
Will Cores Be Taken?: yes no
If yes, proposed zone: N/A

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: N/A

RECEIVED
STATE COMMISSION

APR 9 1991
04-23-1991
DIVISION

Exp. 10/4/91

AFFIDAVIT

200' Alt. IT Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Cherley Mhetra
SPUD DATE 4-11-1991 INIT. CB
LENGTH SURFACE PLANNED 250 of 8 5/8
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE CONDUCTOR
SURFACE PIPE 2 7/8 @ 250
ANHYDRITE T-2084 B-2114 ELEVATION
TD 4510 FORMATION
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2140 Ft. W/ 50 SX
1/2 Base Anyh. @ 1300 Ft. W/ 80 SX
1/2, 1/2 Plug @ 780 Ft. W/ 40 SX
Bottom Surface @ 300 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL No SX (Irr. Well Pond Hauling Hauling)
TECHNICIAN DK DATE
TYPE OF CEMENT 60/40 630 DK
STARTING TIME 1:30 (AM/PM) DATE 4-18-91
COMPLETION TIME 3:45 (AM/PM) DATE 4-19-91
CEMENT COMPANY Allred