

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED
11-15-2002
NOV 15 2002
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

FORM CP-1 (3/92)

API # 15-101-21,486-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate spud or completion date.

WELL OPERATOR MCCOY PETROLEUM CORPORATION KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS P.O. BOX 780208 CITY WICHITA
STATE KANSAS ZIP CODE 67278 CONTACT PHONE # (316) 636-2737
LEASE MOWERY WELL# 1 SEC. 26 T. 19 R. 28 (East/West)
- NW - SW - NW SPOT LOCATION/OOOO COUNTY LANE

3630 FEET (in exact footage) FROM S N (circle one) LINE OF SECTION (NOT Lease Line)
4950 FEET (in exact footage) FROM E W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL XX GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8-5/8" SET AT 306' CEMENTED WITH 150 SACKS
PRODUCTION CASING SIZE 4-1/2" SET AT 4426' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: PERFS 4345-4348'
ELEVATION 2758/2763' T.D. 4690 PBDT 4417 ANHYDRITE DEPTH 2100'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 1) Place 20 sx cement plug in bottom of hole with 2 sx of hulls on Top of cement 2) Add gel spacer to base of Anhydrite at 2100'. 3) Spot 20 sx cement plug across and above Anhydrite. 4) Add gel spacer to base of useable water at 1200'. 5) Cement to surface with approx. 75sx. 6) Cut casing off below plow depth.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? Yes
If not explain why? Logs submitted with original ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Daryl Hanson, McCoy Petroleum Corp. PHONE # (620) 272-1296

ADDRESS P.O. Box 2250 CITY/STATE Garden City, KS 67846

PLUGGING CONTRACTOR Cheyenne Wells Service KCC LICENSE # 6454
(contractor's)

ADDRESS P.O. Box 384, Ness City, KS. 67560 PHONE# (785) 798-2282

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Within 90 days of the application

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: November 14, 2002 AUTHORIZED OPERATOR/AGENT Scott Bump
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

McCoy Petroleum Corporation
453 S. Webb Rd. STE 310
PO Box 780208
Wichita, KS 67278-0208

November 22, 2002

Re: MOWERY #1
API 15-101-21486-00-00
CNWSWNW 26-19S-28W, 3630 FSL 4950 FEL
LANE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor