

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 16 Twp. 16 Rge. (E) 21 (W)

Location as "NE/CNW&SW" or footage from lines C/NW NW
Lease Owner Okmar Oil Company
Lease Name Elmore Well No. 1
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 19 19 71
Application for plugging filed October 19 19 71
Application for plugging approved October 19 19 71
Plugging commenced October 19 19 71
Plugging completed October 19 19 71
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4340 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	382.52'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows: Plugged at 720' with 70 sacks of pozmix; plugged at 350' with 20 sacks of pozmix; plugged at 40' with 10 sacks of pozmix. Plug down at 11:00 P. M. October 19, 1971.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1971
CONSERVATION DIVISION
Wichita, Kansas

10-26-1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 71

Elaine H. Taylor
Elaine H. Taylor Notary Public.

My commission expires December 14, 1973

15-135-20497-00-00

D R I L L E R S L O G

#1 Elmore

CASING RECORD:
376.52' of used 8-5/8"
surface casing.

COMPANY: Okmar Oil Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NW NW
Section 16-16S-21W
Ness County, Kansas

TOTAL DEPTH:
4340'

COMMENCED: October 11, 1971
COMPLETED: October 19, 1971

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Rock & Shale	0	375	Ran 376.52' of used 8-5/8" surface casing; set and cemented at 382.52' with 180 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:45 P. M. October 12, 1971.
Shale	375	786	
Shale w/Sand Streaks	786	975	
Red Bed, Shale & Shells	975	1073	
Sand & Shale	1073	1348	
Red Bed, Shale & Shells	1348	1515	
Shale & Red Bed	1515	1664	
Anhydrite	1664	1700	
Red Bed & Shale	1700	1921	
Shale	1921	2350	
Shale & Lime	2350	2542	
Lime, Shale w/Broken Lime	2542	2668	
Lime & Shale	2668	3910	
Lime	3910	4196	
Lime & Shale	4196	4255	
Lime	4255	4290	
Cherty Lime	4290	4340	

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1971
CONSERVATION DIVISION
Wichita, Kansas

10-26-1971

Rotary Total Depth 4340'

D. & A.

Plugged as follows: Plugged at 720' with 70 sacks of pozmix; plugged at 350' with 20 sacks of pozmix; plugged at 40' with 10 sacks of pozmix. Plug down at 11:00 P. M. October 19, 1971.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 20th day of October, 1971.

My Commission Expires:
December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public