


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-135-20244-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 16 Twp. 16S Rge. 21W (E) (W)
Location as "NE/CNW*SW*" or footage from lines. Approx. 150' E of SE NE
Lease Owner Chief Drilling Company, Inc.
Lease Name Elmore-Ryan Well No. #1
Office Address Box 797, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/30/69 19
Application for plugging filed 4/30/69 19
Application for plugging approved 4/30/69 19
Plugging commenced 4/30/69 19
Plugging completed 4/30/69 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 720' through drill pipe with 70 sacks cement
Plug at 185' through drill pipe with 20 sacks cement
Plug at 40' through drill pipe with 10 sacks cement


RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas
05-05-1969

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF Barton, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Box 797, Great Bend, Kansas 67530
(Address)



Subscribed and sworn to before me this 2nd day of May 1969
Carmen R. Cook
Carmen R. Cook Notary Public.

15-135-2024400-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

ELMORE-RYAN #1
Approx. 150' E of SE NE
Sec. 16-16S-21W, Ness County,
Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 4/22/69
Completed: 4/30/69

Casing Record: 8 5/8" set 290' w/180 sacks cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay	0	40	2333 Gr.
Hard Sand	40	75	2335 D.F.
Shale & sand	75	290	2338 K.B.
Hard cement & shale	290	480	
Sand & shale	480	1470	<u>LOG TOPS</u>
Shale & red bed	1470	1630	Anhydrite 1366 + 972
Anhydrite	1630	1676	Heebner 3717 -1379
Shale & Shells	1676	1870	Toronto 3741 -1403
Shale	1870	2130	Lansing 3764 -1426
Shale & shells	2130	2500	Pawnee 4105 -1767
Shale & lime	2500	4095	Ft. Scott 4191 -1853
Lime	4095	4207	1st Sand 4202 -1864
Lime & shale	4207	4223	2nd Sand 4225 -1887
Lime	4223	4250	Conglomerate 4255 -1917
Shale, sand, & lime	4250	4290	Mississippi 4282 -1944
			Total Depth 4290 -1952
			Log T.D. 4286 -1948

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

05-05-1969

STATE OF KANSAS, COUNTY OF BARTON) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in approximately 150' E of SE NE of Section 16-16S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn to before me this 2nd day of May, 1969.

Carmen R. Cook
Carmen R. Cook, Notary Public



EXPIRES: