

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,612-00-00

LEASE NAME Smeltzer

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3334 Ft. from S Section Line

3094 Ft. from E Section Line

LEASE OPERATOR Morris Oil

SEC. 35 TWP. 19S RGE. 28 (E/W) (W)

ADDRESS 132 East Long, Dighton, KS 67839

COUNTY Lane

PHONE#( 316 ) -397-5874 OPERATORS LICENSE NO. 3684

Date Well Completed 1/19/92

Character of Well D&A

Plugging Commenced 1/19/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/19/92

The plugging proposal was approved on 1/19/92 (date)

by Duane Ranken (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	215'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4700'-2140' 50 sks cement @ 240'

50 sks cement @ 2140' 10 sks cement @ 40'

50 sks cement @ 1070' 10 sks in mousehole

50 sks cement @ 600' 15 sks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor emphasis Oil Operations

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Morris Oil


STATE OF KANSAS COUNTY OF RUSSELL

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506



ABOVE DESCRIBED AND SWORN TO before me this 20th day of January, 1992

[Signature]  
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

RECEIVED  
License No. MMK750  
STATE CORPORATION COMMISSION

JAN 22 1992  
01-22-PP2  
CONSERVATION DIVISION  
Wichita, Kansas

15-101-21612-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Morris Oil  
132 East Long  
Dighton, Kansas 67839

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Smeltzer WELL #1

LOCATION: Approx. SW of NE SE NW  
Section 35-19S-28W  
Lane County, Kansas

LOGGERS TOTAL DEPTH: 4698'

ROTARY TOTAL DEPTH: 4700'

COMMENCED: 1/10/92

CASING: 8-5/8" @ 215' w/160 sks cement

ELEVATION: 2766' K.B.

COMPLETED: 1/19/92

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)


Dakota Sand	750'	Heebner	4010'
Shale	850'	Toronto	4025'
Cedar Hills	1600'	Lansing-Kansas City	4050'
Shale	1780'	Base Kansas City	4419'
Anhydrite	2103'	Marmaton	4449'
Shale	2135'	Mississippi	4683'
Topeka	3735'	R.T.D.	

RECEIVED  
STATE CORPORATION COMMISSION 4700'

JAN 22 1992  
01-22-1992  
CONSERVATION DIVISION  
Wichita, Kansas


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on January 20, 1992.

My commission expires: February 6, 1992.

  
GLENDA R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

  
Glenda R. Tiffin, Notary Public