

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101,21,571-00-00

LEASE NAME Gerald Riley

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 26 TWP. 19 RGE. 28 ~~KRM~~ (W)

ADDRESS 125 N. Market - #1000, Wichita, KS 67202

COUNTY Lane

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed 3-23-91

Character of Well D & A

Plugging Commenced 3-23-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-23-91

The plugging proposal was approved on March 23, 1991 (date)

District #1 Lynn Barlow (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8"	Put in 203'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 50 sx. cement at 2091' thru drill pipe. Spotted 10 sx. cement @ 40'
Spotted 50 sx. cement at 1150' thru drill pipe. w/ wiper plug.
Spotted 50 sx. cement at 600' thru drill pipe. 15 sx. cement in rathole.
Spotted 40 sx. cement at 240' thru drill pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas - Suite 500, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) 401 E. Douglas - Suite 500
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION
04-04-1991
APR 04 1991


SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 91

CONSERVATION DIVISION
Wichita, Kansas

Carolyn J. Tjaden
Notary Public

My Commission Expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. Sept. 5, 1992



15-101-21571-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Ritchie Exploration, Inc., 125 N. Market - #1000, Wichita, KS 67202
 CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
 Wichita, Kansas 67202

Lease Name Gerald Riley Well No. 1
 Sec. 26 T. 19 R. 28W Spot W/2 SE SE
 County Lane State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 210' with 135 sx.
 Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4650'
 Drilling Commenced 3-13-91 Drilling Completed 3-23-91

Formation	From	To	Tops	
Cellar	0	7	Anhydrite	2064
Clay & Shale	7	370	Lansing	4165
Shale	370	1562	Kansas City	4224
Cedar Hill Sand	1562	1945	Cherokee	4500
Shale	1945	2310	Johnson	4600
Shale & Lime	2310	2645	Mississippi	4628
Lime & Shale	2645	2785		
Shale & Lime	2785	3005		
Shale	3005	3210		
Lime & Shale	3210	3375		
Shale & Lime	3375	3860		
Lime & Shale	3860	4650		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 04 1991
 04-04-1991
 CONSERVATION DIVISION
 Wichita, Kansas