

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-101-21,279-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Blue Goose Drilling Company, Inc. OPERATORS LICENSE NO. 5104

ADDRESS P.O. Box 1413 Great Bend, KS 67530 PHONE # (316) 792-5633

LEASE (FARM) Starr WELL NO. 1 WELL LOCATION NE SE NW COUNTY Lane

SEC. 23 TWP. 19 RGE. 28W  or (W) TOTAL DEPTH 4705' PLUG BACK TD 4348'

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A xx SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 304' CEMENTED WITH 190 SACKS

CASING SIZE 5 1/2" SET AT 4400' CEMENTED WITH 120 SACKS

PERFORATED AT 4311-4312'

CONDITION OF WELL: GOOD xx POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand from 4348-4250' (6 sx), 3 sx cement on top of sand, 40 sx @ 2125', 50 sx @ 1250', 40 sx @ 350', 10 sx @ 40-0' (Casing will be pulled).

60/40 posmix, 6% gel. As per directions of Don Ubel, District #1.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8/12/86 8:00 a.m. (Will coordinate with Dist #1).

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Martin E. Miller PHONE # (316) 792-5633

ADDRESS P.O. Box 1413 Great Bend, KS 67530

PLUGGING CONTRACTOR Great Bend Casing Pullers, Inc. LICENSE NO. \_\_\_\_\_

ADDRESS P.O. Box 768, Great Bend, KS 67530 PHONE # (316) 793-9711

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Martin E. Miller  
(Operator or Agent)

07-25-1986  
JUL 25 1986

DATE: 7/24/84



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

OCT 25 '86

EXPIRES

July 25, 1986

WELL PLUGGING NOTICE

Starr #1  
NE SE NW  
Sec. 23-19S-28W  
Lane County

Blue Goose Drilling Company, Inc.  
P. O. Box 1413  
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in black ink, appearing to be "Jm", written over a horizontal line.

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).