

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-21,705-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Rheem Resources, Inc. KCC LICENSE # 31283
(owner/company name) (operator's)
ADDRESS 100 South Main, Suite 505 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-5099

LEASE KALO HINEMAN WELL# 1 SEC. 5 T. 19S R. 28W (East/West)

SW - SE - NE SPOT LOCATION/QQQQ COUNTY Lane

2970' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 20#-8 5/8" SET AT 287.57' CEMENTED WITH 180 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2765'/2770' T.D. 4650' PBDT _____ ANHYDRITE DEPTH 2129'/2165'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill in hole with heavy mud. 1st plug at 2160'-50 sks, 2nd plug at 1320'-80 sks, 3rd plug at 720'-40 sks, 4th plug at 330'-40 sks, 5th plug at 40'-10 sks, 15 sks rathole, Total 235 sks of 65/35 posmix, 6% gel, 3% CC, 1/2# Floseal per sk.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? NO

If not explain why? Has been sent to operator for completion.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# (913) 743-5443

ADDRESS P.O. Box 294 City/State Wakeeney, Kansas

PLUGGING CONTRACTOR Abercrombie, RID, Inc. KCC LICENSE # _____

ADDRESS 150 N. Main, Suite 801 Wichita, Ks. 67202 (company name) (contractor's)
PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4:00 a.m. on 7-17-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-28-95 AUTHORIZED OPERATOR/AGENT: Jack K. Wharton Jack K. Wharton
(signature) Vice President

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1995
CORV. DIVISION
WICHITA, KANSAS