

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-23,301-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Dunne Oil Company OPERATORS LICENSE NO. 4197

ADDRESS 100 S. Main, #520, Wichita, KS 67202 PHONE # (316) 267-3448

LEASE (FARM) Elmore WELL NO. 1-3 WELL LOCATION 70' NE W/2 W/2 COUNTY Ness

SEC. 3 TWP. 16S RGE. 21 ~~(E) (W)~~ TOTAL DEPTH 4362' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A xx SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 236' CEMENTED WITH 150 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD xx POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Circulate heavy mud in hole. 1st plug

1710'-50 sx. 2nd plug 870'-80 sx. 3rd plug 260'-40 sx. 4th plug 40'-10 sx. Rathole-15 sx.

All cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? No
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 3:30 a.m. on 10-30-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Bill Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 542

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 11-11-88

RECEIVED
NOV 15 1988
11-15-1988
CONSERVATION DIVISION
Wichita, Kansas