

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3959
Name: Siroky Oil Management, Inc.
Address 1: P.O. Box 464
Address 2: _____
City: Pratt State: KS Zip: 67124 + _____
Contact Person: Brian Siroky
Phone: (620) 672-5625
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 4271
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-30266 · 00 · 00
Spot Description: EZSENE
_____ Sec. 22 Twp. 30 S. R. 7 East West
3,300 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Crumley Well #: 1-3D
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 04/21/2003
Plugging Completed: 04/28/2003


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	252	none
			5 1/2"	4270	710'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

sand @ 4150, bail 5 sxs cement. Shot pipe @ 1203', 710'. pumped 35 sxs cement @ 1130', pull to 300 and circulate with 55 sxs cement.

RECEIVED
FEB 23 2012
KCC WICHITA

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US 56 Hwy. Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-6964
Name of Party Responsible for Plugging Fees: Siroky Oil Management, Inc.
State of Kansas County, Pratt, ss.
Brian Siroky, President Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AK

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
4/30/2003	399

Bill To
Siroky Oil Management Inc. Box 464 Pratt, KS 67124

P.O. No.	Terms	Lease Name
	net	Crumley I-3D

Description	Qty	Rate	Amount
Rig Time	22.5	120.00	2,700.00T
Trucking		90.00	90.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Shots	2	140.00	280.00T
Torch		35.00	35.00T
Water Truck	4	55.00	220.00T
Backhoe	6	60.00	360.00T
Phone Calls		5.00	5.00T
Clerical Fees		10.00	10.00T
Out of Town		120.00	120.00T
<p>4/21/03 – 4.5 hrs. Drove to location, tore tubing head apart. Had to level out spot for rig. Rigged up and checked hole. Drove in.</p> <p>4/22/03 – 10 hrs. Drove to location, sanded off bottom. Dug cellar and pit. Unpacked casing head, had already been cemented to surface. Cut surface off, checked hole. Sand at 4150, bailed 5 sacks cement. Shot pipe at 1203, 710. Dug cellar out on 1-4D, wasn't squeezed. Ran 33 joints, stacked out on mud. Drove in.</p> <p>4/23/03 – 3.5 hrs. Drove to location, waited on cement. Started raining, road got to wet to get trucks in. Shut down and drove in.</p>			
		Subtotal	

RECEIVED
FEB 23 2012
KCC WICHITA

Sales Tax (6.3%)

Total

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
4/30/2003	399

Bill To
Siroky Oil Management Inc. Box 464 Pratt, KS 67124

P.O. No.	Terms	Lease Name
	net	Crumley I-3D

Description	Qty	Rate	Amount
4/28/03 - 4.5 hrs. Drove to location, pumped 35 sacks cement at 1130, pulled to 300 and circulated with 55 sacks cement. Layed tubing dopwn, tore down and loaded out.			

RECEIVED FEB 23 2012 KCC WICHITA	Subtotal	\$3,900.00
	Sales Tax (6.3%)	\$245.70
	Total	\$4,145.70