

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 3344 Name: Magnum Oil & Gas Inc Address 1: 8520 25th Ave City: Greensburg State: KS Zip: 67054 Type of Well: Gas Well Is ACO-1 filed? No Producing Formation(s):

API No. 15 - 097-21441-00-00 Spot Description: SW SW NE SW SE-SE-NW-SE Sec. 18 Twp. 29 S. R. 18 1-358 1461 Feet from South Line of Section 4-369 3790 Feet from East Line of Section GPS-KCC Footages Calculated from Nearest Outside Section Corner: SE SW Date Well Completed: 1/31/12 The plugging proposal was approved on: 2/1/12 by: Eric Maclaren (KCC District Agent's Name)

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Pulled Out). Includes data for 8-5/8" and 4-1/2" casings.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Check hole, BP@4000'. Dumped 2sx cement. Got 23" stretch. Tried cutting @ 2800', 2600', 2400'. Came loose @ 2239'. Pulled up to 1240'. Copeland pumped 15gel 50sx @ 1240'. Pulled up to 600', pumped 50sx 60/40poz 4% gel. Pulled up to 360', pumped 50sx. Pulled up to 40', pumped 20sx. Circulated cement to surface. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc. Address 1: PO Box 467 City: Chase State: KS Zip: 67524 Phone: (620) 938-2943

RECEIVED FEB 23 2012

Name of Party Responsible for Plugging Fees: Magnum Oil State of KS County, Rice Mike Kelso (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

Handwritten initials