

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30481  
Name: Apollo Energies, Inc.  
Address 1: 10378 N 281 Hwy  
Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Contact Person: Kevin Fischer or Jim Byers  
Phone: (620) 672-9001  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 175-21299-00-00  
Spot Description: \_\_\_\_\_  
SE NW NW NE Sec. 1 Twp. 32 S. R. 31  East  West  
4.845 Feet from  North /  South Line of Section  
2.265 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Seward  
Lease Name: Saunders Well #: 1-1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 6/7/2010 (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Plugging Commenced: 1/3/12  
Plugging Completed: 1/6/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	1721	700 Sacks Cement
		Production	5.5	6054	260 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 60 bbls. water to kill well. Started out with tubing; tubing hung up after six joints. Could not work tubing free. Had Log-Tech shoot tubing, packer came free. Pulled tubing out. Cut surface casing off 4' below ground. Checked hole; sand at 5430'. Bailed 5 sacks cement on sand & ripped casing at 2300'. Ripped casing at 2000' & 1900'. Pipe came free at 1900'. Pulled casing up to 1740' & pumped 15 gel, 200# hulls & 50 sacks cement. Pulled to 500' & pumped 50 sacks cement. Pulled to 40' & pumped 25 sacks cement. Topped off well with 10 sacks cement.

Plugging Contractor License #: 31925 Name: Quality Well Service  
Address 1: 190th US 56 Highway Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3410  
Name of Party Responsible for Plugging Fees: Apollo Energies, Inc.  
State of Pratt County, Kansas, ss.  
Kevin R. Fischer  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

RECEIVED

FEB 23 2012

**Quality Well Service, Inc.**

**190 US Highway 56  
Ellinwood, KS 67526**

**Invoice**

Date	Invoice #
1/17/2012	1347

Bill To
Apollo Energies Inc 10378 N. 281 Hwy Pratt, KS 67124

P.O. No.	Terms	Lease Name
	Net	Saunders 1-i

Description	Qty	Rate	Amount
Drove to location, ripped casing at 2000' & 1900'. Pipe came free at 1900'. Pulled casing up to 1740' & pumped 15 gal, 200# hulls & 50 sacks cement. Pulled to 500' & pumped 50 sacks cement. Pulled to 40' & pumped 25 sacks cement. Tore down floor and rig & topped off well with 10 sacks cement. Cleaned up location & pulled trucks out with backhoe.			

<b>Subtotal</b>	\$9,465.00
<b>Sales Tax (7.55%)</b>	\$714.61
<b>Total</b>	\$10,179.61

**RECEIVED  
FEB 23 2012  
KCC WICHITA**

**Quality Well Service, Inc.**

**190 US Highway 56  
Ellinwood, KS 67526**


**Invoice**

Date	Invoice #
1/17/2012	1347

Bill To
Apollo Energies Inc 10378 N. 281 Hwy Pratt, KS 67124

P.O. No.	Terms	Lease Name
	Net	Saunders 1-1

Description	Qty	Rate	Amount
Rig Time	38	190.00	7,220.00T
Floor Rental	1	175.00	175.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Rip Casing	2	400.00	800.00T
Welding	1	75.00	75.00T
Water Truck	5.5	80.00	440.00T
Backhoe	3.5	80.00	280.00T
Out of Town	3	120.00	360.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
<p>1/3/12: Drove to location, had dozer pull rig in. Raised pole, changed over for tubing &amp; drove to motel.</p> <p>1/4/12: Drove to location, pumped 60 bbls. water to kill well. Started out with tubing; tubing hung up after six joints. Could not work tubing free. Had Log-Tech shoot tubing, packer came free. Pulled tubing out &amp; drove to motel.</p> <p>1/5/12: Drove to location, sanded off bottom &amp; loaded hole with water. Dug cellar, unpacked casing head &amp; set floor. Cut surface off 4' below ground. Checked hole; sand at 5430'. Bailed 5 sacks cement on sand &amp; ripped casing at 2300'. Drove to motel.</p> <p>1/6/12:</p>			

 <b>RECEIVED</b> <b>FEB 23 2012</b> <b>KCC WICHITA</b>	<b>Subtotal</b>
	<b>Sales Tax (7.55%)</b>
	<b>Total</b>

QUALITY WELL SERVICE INC

324 SIMPSON  
PRATT KS 67124

**Invoice**

Date	Invoice #
1/9/2012	366

Bill To
APOLLO ENERGIES 10378 N 281 HWY PRATT KS 67124

P.O. No.	Terms	Project

Quantity	Description	Rate	Amount
83	COMMON	13.50	1,120.50T
52	POZ	8.50	442.00T
20	GEL	20.00	400.00T
2	HULLS	35.00	70.00T
155	HANDLING	2.10	325.50T
2,700	.08 * SACKS * MILES	0.08	216.00T
1	PLUG	950.00	950.00T
20	PUMP TRUCK MILEAGE	8.00	160.00T
1	ADDITIONAL DAY	300.00	300.00T
199.2	DISCOUNT	-1.00	-199.20T
	SAUNDERS #1-1 Sales Tax SEWARD	7.55%	285.75



**RECEIVED**

Thank you for your business.	<b>FEB 23 2012</b>	<b>Total</b>	\$4,070.55
------------------------------	--------------------	--------------	------------

**KCC WICHITA**

# QUALITY WELL SERVICE, INC.

Federal Tax I.D. # 481187368

5341

Home Office 324 Simpson St., Pratt, KS 67124

Todd's Cell 620-388-5422  
Office / Fax 620-672-3663

Rich's Cell 620-727-3409  
Brady's Cell 620-727-6964

Date	1-6-12	Sec.	1	Twp.	32	Range	31	County	SEWARD	State	K-S	On Location	Finish
Lease	S.A. R.		Well No.		Location								
Contractor	QWS				Owner APOLLO ENERGIES INC								
Type Job	Plug				To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.								
Hole Size	17 1/4"		T.D.		6055								
Csg.	5 1/2		Depth		6054								
Tbg. Size			Depth		Charge To APOLLO ENERGIES INC.								
Tool			Depth		Street 10378 N 231 Hwy								
Cement Left in Csg.			Shoe Joint		City PRATT State K-S.								
Meas Line			Displace		The above was done to satisfaction and supervision of owner agent or contractor.								
					Cement Amount Ordered 135 SKS <sup>6054-6110</sup> <del>135 SKS</del>								
<b>EQUIPMENT</b>													
Pumptrk	No.	6		Rack		Common		15 gals					
Bulktrk	No.	7		Cable		Poz. Mix		83					
Bulktrk	No.					Gel.		52					
Pickup	No.					Calcium		20					
<b>JOB SERVICES &amp; REMARKS</b>					Hulls 2								
Rat Hole					Salt								
Mouse Hole					Flowseal								
Centralizers					Kol-Seal								
Baskets					Mud CLR 48								
D/V or Port Collar					CFL-117 or CD110 CAF 38								
1st plug 2 Hulls 15 gal, 50 SKS at 1740'					Sand								
					Handling 1.55								
					Mileage 20								
2nd plug 500' 50 SKS					<b>FLOAT EQUIPMENT</b>								
					Guide Shoe								
3rd plug 40' 25 SKS					Centralizer								
					Baskets								
Tapp off 10 SKS					AFU Inserts								
					Float Shoe								
					Latch Down								
1-3-12 killed well pumptrk 40 BRL water													
					Pumptrk Charge PTH								
					Mileage 20								
					Tax								
					Discount								
					Total Charge								
X Signature <i>[Signature]</i>													

**RECEIVED**  
**FEB 23 2012**  
**KCC WICHITA**