


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15007-206800000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 30 Twp. 31S Rge. 11 R/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
C E/2 E/2 NW

Lease Owner Graves Drilling Co., Inc.
Lease Name CHAIN RANCH Well No. 1
Office Address 910 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed November 1 1978
Application for plugging filed November 1 1978
Application for plugging approved November 1 1978
Plugging commenced November 1 1978
Plugging completed November 1 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4366
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 210'. Pumped 40 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John C. Graves (~~employee of owner~~) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 78

My commission expires January 18, 1982

RECORDED
STATE CORPORATION COMMISSION

Dorothy Galbraith
Notary Public.



NOV 14 1978

CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS LOG

15-007-20680-0000

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas. 67202

DRILLING COMMENCED: October 24, 1978

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: November 1, 1978

CASING RECORD: 5 Jts. 211' of used 8-5/8"
cemented with 185 sacks

LOCATION: CHAIN RANCH NO. 1
E/2 E/2 NW/4
Section 30-31S-11W
Barber County, Kansas.

0	-	25	Sand
25	-	211	Red Bed
211	-	2044	Shale and Lime
2044	-	2610	Lime and Shale
2610	-	3197	Shale and Lime
3197	-	3668	Lime and Shale
3668	-	3868	Sand and Lime
3868	-	4142	Lime and Shale
4142	-	4236	Shale and Lime
4236	-	4317	Lime
4317	-	4366	Chert
		4366	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.


GRAVES DRILLING CO., INC.

By *Betty Brandt*
Secretary-Treasurer

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, this 10th day of November, 1978.

Dorothy Galbraith
Dorothy Galbraith Notary Public



GRAVES DRILLING CO., INC.
11/10/78