

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15101 20541-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 15 TWP. 17S RGE. 28W E/W
 Location as in quarters or footage from lines:
 SW SW SW

Lease Owner A. Scott Ritchie
 Lease Name Richards L-1 Well No. _____
 Office Address suite 950 125 N. Market Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3-25-82
 Plugging completed 3-31-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	328'	none
				4-1/2"	4649'	2616'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 30 sacks cement and 1 sack hull on bottom and pushed plug to 3400'. Shot casing @3374', 3283', 3003', 2915', 2825', 2736', 2633' and pulled ~~XXXXXX~~ 59 joints of pipe.
Plugged well with 1 sack hulls, 30 sacks 50/50 pos 2% gel, 18 sacks gel, 8-5/8" plug
40 sacks 50/50 pos, 2% gel, 7 sacks gel, 1 sack hulls, 10 sacks 50/50 pos 2% gel.
 Plugging Complete.

RECEIVED
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling


APR - 8 1982
 4-8-82
 CONSERVATION DIVISION
 Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 82

My Commission expires:



Irene Hoover
 Notary Public.