


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Lane _____ County, Sec. 15 Twp. 17 Rge. 28 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Mull Drilling Company
Lease Name Richards Well No. 1
Office Address 415 Page Court, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/27/76 19
Application for plugging filed 11/27/76 19
Application for plugging approved 11/27/76 19
Plugging commenced 11/27/76 19
Plugging completed 11/27/76 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4630 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	288	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug at 850' with 70 sacks
2nd plug at 250' with 20 sacks
3rd plug at 40' with 10 sacks
2 sacks in rathole
Job complete at 1:pm 11/27/76
DEC 04 1976
12-1-76

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Co., Inc.
Address 408 One Twenty Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick ss.
James C. Remsberg (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
408 One Twenty Building, Wichita 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of December 19 76

My commission expires January 17, 1977
Mary Lou Taylor
Mary Lou Taylor Notary Public.



DRILLERS LOG

15-101-20196-0000

OPERATOR Mull Drilling Company, Inc.
415 Page Court
Wichita, Kansas 67202

LEASE Richards No.1
C SW SE Sec. 15-17S-28W
Lane County, Kansas

CONTRACTOR Slawson Drilling Company, Inc.
408 One Twenty Building
Wichita, Kansas 67202

COMMENCED 11/15/76

COMPLETED 11/27/76

RTD 4630'

CASING: 279.81' new 8-5/8" set at 288' with 225 sx cement

0' to 291' 12½" Surface Hole
291' to 1427' Shale & Shells
1427' to 2128' Shale & Sand
2128' to 2160' Anhydrite
2160' to 2794' Shale
2794' to 3042' Shale & Lime
3042' to 3272' Lime & Shale
3272' to 3424' Shale & Lime
3424' to 3791' Lime & Shale
3791' to 3940' Shale & Lime
3940' to 4106' Lime & Shale
4106' to 4415' Lime
4415' to 4430' Lime & Shale
4430' to 4535' Lime
4535' to 4603' Shale & Lime
4603' to 4360' Lime & Shale
4630 RTD

DEC 07 1976

STATE OF KANSAS
SEDGWICK COUNTY

I, James C. Remsberg of the Slawson Drilling Company, Inc.
hereby state that the above and foregoing is a true and correct copy of
the log of the Richards No. 1 well.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me on December 4, 1976

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1977

