

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

-0000

API NUMBER 15-101,21,045

LEASE NAME Richards

WELL NUMBER #1

SPOT LOCATION N/2-SE-NE

SEC. 17 TWP. 17 RGE. 28 (E) of 17

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-20-85

Plugging Completed 5-30-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 405 Century Plaza Bldg, Wichita, Ks. 67202

PHONE 316-682-4101 OPERATORS LICENSE NO. 5088

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,653'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	345'	None
				5-1/2"	4,578'	1,442.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Dumped sand to 3,930' and 5 sacks cement. Shot casing at 3800', 3000', 2500', 1750' and 1500'. Pulled 40 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 400 psi and shutin 200 psi

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or 6-11-85  
(operator) of above-described well, being first duly sworn on oath, says I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) James W. Rockhold  
Box 698, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 10th day of June, 1985

NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman  
Notary Public