


STATE OF KANSAS
STATE CORPORATION COMMISSION

15101-20273-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 18 Twp. 17 Rge. 28 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SW NE NW
Lease Owner Mull Drilling Company
Lease Name Fuller #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/29/78 _____ 19____
Plugging completed 12/28/78 _____ 19____
Reason for abandonment of well or producing formation _____
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4593
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	322	none
				5 1/2	4605	3309'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4300' and ran 4 sacks cement. Loaded hole, shot pipe at 3782', 3317', pulled 79 joints. Pumped 3 sacks hulls, 70 sacks cement, 20 sacks gel and 60 sacks cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

JAN 15 1979
1-15-79
COMMERCIAL STATE
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of Jan., 19 79

NOTARY PUBLIC
MARGARET MITCHELL
Rice County, Ks
My Comm. Exp. Feb. 15

Margaret Mitchell
Notary Public.

My commission expires _____

WELL LOG
Fuller #1
SW NE NW Sec. 18-17S-28W
Lane County, Kansas

Name of Operator: Mull Drilling Co., Inc.
415 Page Court, 220 W. Douglas
Wichita, Kansas 67202


Date Completed: January 8, 1978

<u>FROM</u>	<u>TO</u>	
0	330	Shale & sand
330	632	Shale
632	1825	Shale & Sand
1825	2177	Shale
2177	2208	Anhydrite
2208	2340	Shale & Sand
2340	2635	Shale & shells
2635	2830	Shale & lime
2830	3010	Shale & shells
3010	3170	Shale
3170	3345	Shale & lime
3345	3485	Shale & shells
3485	3960	Shale & lime
3960	4120	Lime
4120	4272	Shale & lime
4272	4305	Lime
4305	4460	Shale & lime
4460	4530	Lime
4530	4556	Shale & Lime
4556	4570	Lime
4570	4595	Shale & Lime
4595		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss

George E. Miller, Jr.; President of Blue Goose Drilling Co., Inc.
being first duly sworn on oath says: That I have knowledge of the facts,
statements and matters herein contained and the log of the above described well
as filed and that the same are true and correct.


George E. Miller, Jr.

Subscribed and sworn before me this 9th day of January, 1978.


Notary Public Barton County

My Commission Expires 8-1-81

