

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-21,639-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123
(owner/company name) (operator's)

ADDRESS 110 N. Market, Suite 205 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Becker "L" WELL# 1 SEC. 31 T. 16S R. 27W (~~East~~ West)

- NW - NE - NW SPOT LOCATION/QQQQ COUNTY Lane

4950 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

3630 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 299'KB CEMENTED WITH 170sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2732/2737 T.D. 4675 PSTD _____ ANHYDRITE DEPTH 2150(+587)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING 50sx @ 2180', 80sx @ 1380', 40sx @ 700', 40sx @ 330',
10sx w/bridge plus @ 40', 15sx rathole of 60/40 poz, 6% gel + 1/4# floseal per sx.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Doyle Folkerts PHONE# (316) 793-5742

ADDRESS P.O. Box 1303 City/State Great Bend, Kansas 67530

PLUGGING CONTRACTOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123

ADDRESS 110 N. Market, Suite 205 (company name) Wichita, KS PHONE # (316) 262-8427 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Complete @ 1:15 AM on 11/16/92

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-20-92 AUTHORIZED OPERATOR/AGENT: C.W. Sebitt

C.W. Sebitt (signature) President

NOV 23 1992
11-23-1992
DIVISION