



15-101-19001-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

03-30-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: William F. Roland Est., R. O. Thompson, Admr.,

Complete Address: Chapin Building, Medicine Lodge, Kansas.

Lease Name: Gates Well No. 1

Location: CSW-SE Sec. 19 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4656 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

271'--8 5/8" Surface casing cement circulated with 225 Sx.

4350'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 4194'. No plug back indicated.

Push plug to 4100', sand back to 4050' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement staged.

Very truly yours,

*K. L. Nichol*  
Conservation Division Agent