


15-169-00830-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Saline County. Sec. 31 Twp. 15 Rge. 3 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NW/4 SW/4 NW/4
Lease Owner Shields Oil Producers,
Lease Name Shields Oil Producers-Bengston Well No. 3.
Office Address Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed June 26 1951
Application for plugging filed December 3 1956
Application for plugging approved December 4 1956
Plugging commenced Dec. 10, 1956
Plugging completed Dec 15 1956
Reason for abandonment of well or producing formation Depleted well

If a producing well is abandoned, date of last production November 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Rule Durkey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|--------|----------------|
| | | | | 8 5/8" | 350' | cmtd w/100 sax |
| | | | | 12 1/2" | 64' | cmtd w/150 sax |
| | | | | 5 1/2" | 3417' | 2930 1/2' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3430 feet to surface feet for each plug set.

Hole filled with sand from 3430 to 3405; six sacks of cement placed in hole with dump bailer; Mudded hole to 190 ft; ten foot rock bridge installed from 190 ft to 180; fifteen sacks of cement poured into hole filling hole to 25 ft; rock bridge installed and hole capped with five sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pine Culling Co
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Shields Building - Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1956

My commission expires 12-18-1957

Jack P. Beeman
Notary Public.

PLUGGING
FILE SEC 31 T. 15 R. 3W
BOOK PAGE 122 LINE 6

STATE CORPORATION COMMISSION
DEC 21 1956 12-21-56
CONSERVATION DIVISION
Wichita, Kansas

15-169-00830-00-00

WELL LOG

SHIELDS OIL PRODUCERS
Bengtson #3

NW/4 SW/4 NW/4
Section 31, Township 15S, Range 3W
Saline County, Kansas

Total Depth: 3418'
Commenced: June 7, 1951
Completed: June 26, 1951
Contractor: Honaker Drilling Co., Inc.

CASING RECORD

| Size | Run | Cemented |
|--------|-------|----------|
| 12 1/2 | 64' | 150 sax |
| 8 5/8 | 350' | 100 sax |
| 5 1/2 | 3417' | 75 sax |

Surface Elevation: 1302 RB
Treatment: 1000 gallons Acid
Production: (Swabbed 5) Bbl. - 4 Hrs.)
280 Bbl.

----- Figures Indicate Bottom of Formation -----

| | | | |
|-----------------|------|----------------|-----------|
| Top Soil & Clay | 35 | Shale | 2350 |
| Gravel | 50 | Shells & Shale | 2410 |
| Shale & Shells | 61 | Lime | 2715 |
| Shale & Shells | 340 | Shale & Lime | 2980 |
| Lime | 355 | Lime | 3060 |
| Lime | 660 | Lime | 3135 |
| Lime and Shale | 875 | Lime & Shale | 3180 |
| Lime | 965 | Lime & Shale | 3330 |
| Lime & Shale | 1530 | Shale | 3380 |
| Lime & Shale | 1925 | Lime & Shale | 3418 T.D. |
| Lime | 2025 | | |

NOTES

Plug Drilled ----- June 26, 1951

Maq. Dol. 3417'

PLUGGING
 SEC 31, T. 15, R. 3W.
 BLOCK PAGE 12211 F 6

STATE OF KANSAS
 DEC 4 - 1956
 CONSERVATION DIVISION
 Wichita, Kansas