


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-101 20151 - 00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Layne County. Sec. 36 Twp. 16 Rge. 27w E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____
SE SE NW
Lease Owner O.A. Sutton
Lease Name Bailey Well No. 1
Office Address 800 Sutton Place Wichita Ka. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

OIL
Date Well completed 4/ 1975
Application for plugging filed 9/ 1976
Application for plugging approved 9/ 1976
Plugging commenced 10/ 12 1976
Plugging completed 10/18 1976
Reason for abandonment of well or producing formation _____

Dry
If a producing well is abandoned, date of last production 3/10/ 1976

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation K.C. Depth to top 4460 Bottom 4469 Total Depth of Well 4618
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Clay & shale</u>	<u>Surface</u>	<u>0</u>	<u>322</u>	<u>8 5/8</u>		
		<u>0</u>	<u>4618</u>	<u>5 1/2</u>		<u>1530</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 4450 dumped, 3 ex. cement

Squeezed top with Halliburton pumped in 3 ex hulls 70 ex cement
10 ex jell release plug and pump 60 ex cement pumped in under 800
lbs. max. preasure, all cement was 50-50 perz, 6% jell

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Nicholas Casing Pulling

STATE OF Kansas COUNTY OF Sedwick, ss.
Wilbur Burg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George H. Nicholas

(Address) _____

before me this 18th day of October, 1976



Glenn M. Stegman
Notary Public.

My commission expires 7-6-77

15-101-20151-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Bailey #1
SE-SE-NW Sec 36-16S-27W
Lane County Kansas

Commenced: 7-24-75

Completed: 8-6-75

OPERATOR: O. A. SUTTON

Depth		Formation	Remarks
From	To		
0	326	Surface Clay-Shale	Ran 8 jts of used 8 5/8" 28# csg set @ 322' Cemented w/ 225 sks Common 2% Gel 3% CC PD @ 6:45 p.m. 7-24-75
326	922	Shale	
922	1002	Sand	
1002	1613	Shale	
1613	1780	Sand	
1780	2062	Shale	
2062	2109	Anhy	Ran 113 jts of New 15 1/2" 5 1/2" csg set @ 4619' Cemented w/100 sks Salt Sat Posmix PD @ 4:15 a.m. 8-6-75
2109	2201	Shale	
2201	2611	Shale-Lime	
2611	3264	Lime-Shale	
3264	3546	Lime	
3546	3726	Lime-Shale	
3726	4619	Lime	
	4619 - TD		

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled SE-SE-NW Sec 36-16S-27W, Lane County Kansas to the best of my knowledge and belief.

09-21-1974 
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18th day of August, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

