

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,698-00-00

LEASE NAME Munsell

WELL NUMBER #1

1065 Ft. from S Section Line

1420 Ft. from E Section Line

SEC. 31 TWP. 16 RGE. 27 ~~W~~ or (W)

COUNTY Lane

Date Well Completed 3/23/95

Plugging Commenced 3/23/95

Plugging Completed 3/23/95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Reynolds-Rexwinkle Oil, Inc.

ADDRESS 212 N. Market, #402, Wichita, KS 67202

PHONE# (316) 269-1233 OPERATORS LICENSE NO. 30870

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/23/95 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4600 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From	To	Size	Put in	Pulled out
		259'	0'	8-5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged with 255 sacks 60/40 Pozmix, 6% gel, 1/4# floeal per sack as follows: 50 sx @ 2160', 80 sx @ 1300', 50 sx @ 660', 40 sx @ 280', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 7:00 p.m. 3/23/95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Reynolds-Rexwinkle Oil, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Daniel M. Reynolds (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Daniel M. Reynolds

(Address) 212 N. Market #402 67202

SUBSCRIBED AND SWORN TO before me this 9th day of May, 1995

Sharon K. Garrison
 Notary Public



Commission Expires: 6/4/96