

1 030514

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,214 - 00-00

C NE NW, SEC. 20, T 16 S, R 27 W/EX

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Kirk Well # 1-20

Operator: Gear Petroleum Co., Inc.

County Lane Lane 157.13

Name: 300 Sutton Place

Well Total Depth 4650 Mississippi feet

Address Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 10 Month: September Year: 1985

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2175'
Elevation 2724 KB

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 60 sx cement

3rd plug at 360' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Clyde Wiley

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 pm Day: 10 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1110' with 60

sx cement, 3rd plug at 360' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

(Buyer/Client not) observe this **RECEIVED**

SEP 17 1985

STATE CORPORATION COMMISSION

Signed Steve Dumont
(TECHNICIAN)

DATE

INV. NO. 10118

SEP 16 1985
09-16-1985
CONSERVATION DIVISION