

To: 1 000031
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-21,729 0000
C NW, SEC. 20, T. 16 S, R. 27 W/EX
3960 feet from S section line
3960 feet from E section line
Lease Name Albin "OTM" Well # 1

TECHNICIAN'S PLUGGING REPORT 12-11
Operator License # 6039
Operator: L.D. Drilling, Inc./Rheem Resources
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

County Lane Lane 150.47
Well Total Depth 4630 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 11 Month: 12 Year: 1996

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2136-69'
1st plug at 2170' with 50 sx cement, 2nd plug at 1370' with 80 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 330' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 11 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement,
2nd plug at 1370' with 80 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 330' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOLVED
I, Kevin D. Stute observe this plugging.

DATE DEC 13 1996

INV. NO. 47179
12-11 553 17 1997

Signed Kevin D. Stute
(TECHNICIAN)

FOR KCS USE:

EFFECTIVE DATE: 9-17-96

DISTRICT # 3

SGA7 Yrs 8 1/2

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

State of Kansas

NOTICE OF INTENTION TO DRILL 101-21,729-00-00

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 26 1996
month day year

Spot NW Sec 20 Twp 16 S. Rg 27 East

OPERATOR: License # 6039
Name: L. D. DRILLING, INC./RHEEM RESOURCES, INC.
Address: R.R. 1 Box 183 B
City/State/Zip: Great Bend, Kansas 67530
Contact Person: L.D. Davis
Phone: (316) 793-3051

3960 feet from South / North line of Section
3960 feet from East / West line of Section
IS SECTION X REGULAR INREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Lane

Lease Name: ALBIN "OTM" Well #: 1

Field Name:

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Lansing-Kansas City

Nearest lease or unit boundary: 990'

Ground Surface Elevation: est. 2550 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 220'

Depth to bottom of usable water: 1360'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 300'

Length of Conductor pipe required: none

Projected Total Depth: 4600'

Formation at Total Depth: Mississippi

Water Source for Drilling Operations: well term pend X other

DWR Permit #:

Will Cores be Taken?:

If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OAWD Disposal Wildcat Cable
Seismic: # of Holes Other

If OAWD: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:

Bottom Hole Location:

Exp. 3/12/97

AFFIDAVIT 200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be...

Pusher 6099
SPUD DATE 12-2-96 INIT. KS

LENGTH SURFACE PLANNED 300
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 309 CONDUCTOR
ANHYDRITE T-2174 B-2179 ELEVATION

TD 4630 FORMATION
DRAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Plug./Council @ Ft. W/ SX

Anhydrite Base @ 2170 Ft. W/ 50 SX

1/2 Base Anyh. @ 1370 Ft. W/ 80 SX

1/2, 1/2 Plug @ 700 Ft. W/ 40 SX

Bottom Surface @ 330 Ft. W/ 40 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond X)
Hauling

TECHNICIAN SM DATE 12-10-96

TYPE OF CEMENT 60/40 6% 14K/10 Sand

STARTING TIME 2:30 (AM/PM) DATE

COMPLETION TIME 5:30 (AM/PM) DATE 12-11-96

CEMENT COMPANY Allied

12-12-1996

RECEIVED
KANSAS COMMISSION
OCT 12 1996