

1 040163

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 200'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,092 *OR*
S NE NE, SEC. 20, T 16 S, R 27 W/E

4420 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name Foster Well # 1

Operator: Mid-Continent Energy Corp.

County Lane Lane 149.83

Name & Address 120 South Market, Suite 712

Well Total Depth 4610 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Co. License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 5:00 am Day: 28 Month: November Year: 19 84

Plugging proposal received from Don Kern

(company name) Allen (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2120' with 50 sx cement

2nd plug at 1010' with 60 sx cement

3rd plug at 400' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Edgar Knobloch
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:45 am Day: 28 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement, 2nd plug at 1010' with

60 sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie.
(If additional description is necessary, use BACK of this form.)

INVESTIGATOR (check / circle) observe this plugging.

DATE 12-13-84

Signed Edgar Knobloch
(TECHNICIAN) *SD*

REV. NO. 5969