

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,920-00-00

SE SE, Sec. 14, T 16 S, R 27 ~~W~~ ~~EX~~

330 feet from ~~N~~/S section line

330 feet from ~~N~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Clarence Well # 1-14

Operator: Gear Petroleum Co., Inc.
Name & 300 Sutton Place
Address Wichita, KS 67202

County Lane

Well Total Depth 4620 feet 150.15

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 4 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Marior Burris

(company name) Warrior (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2070' with 50 sx cement

2nd plug at 1500' with 50 sx cement

3rd plug at 390' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

7th plug to circulate mousehole with 10 sx cement Signed R. Bearlutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 pm Day: 4 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement, 2nd plug at 1500' with

50 sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied # 41001

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1984

CONSERVATION DIVISION
Wichita, Kansas

03-07-1984

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed R. Bearlutton
(TECHNICIAN)

INV. NO. 3613