

To: 060713  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,237-00-00  
N1/4SW1/4SEC. 13, T16 S, R 27 W1/4  
2630 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5751

Lease Name Horschem Well # 1-13

Operator: Gear Petroleum Co. Inc.  
Name & Address: 300 Sutton Place  
Wichita, Kansas  
67202

County Lane 150.80  
Well Total Depth 4640 feet  
Conductor Pipe: Size \_\_\_\_\_ feet ✓  
Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Co License Number 5302

Address Wichita, Kansas 67202

Company to plug at: Hour: 1:00 PM Day: 6 Month: November Year: 19 85

Plugging proposal received from Bruce Fickel

(company name) Red Tiger Drilling Co. Inc. (phone) 316-263-2371

work: 1st plug @ anhydrite w/ 50 lbs 2nd plug base of Cheyenne  
w/ 70 lbs 3rd plug 30' out of surface w/ 50 lbs 4th plug  
40' to 0' on solid bridge w/ 10 lbs 5th plug circulate 10 lbs  
in rat hole.

Chr. 2674-

Anhydrite 2067 to 2107.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 PM Day: 6 Month: November Year: 19 85

ACTUAL PLUGGING REPORT

1st plug @ 2110' w/ 50 lbs cement. 2nd plug  
@ 950' w/ 70 lbs cement. 3rd plug @ 370' w/ 50 lbs cement.  
4th plug @ 40' on solid bridge w/ 10 lbs cement. 5th plug  
circulated 10 lbs cement through one joint of pipe.

The hole was filled w/ heavy mud & circulated 10 min  
before pumping the first plug & filled hole w/ heavy mud between

Remarks: Each plug. Allied Cementing pumped 60/40 ports w/ 6 7/8" cell  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 25 1985

INV. NO. 11184

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Paul A. Luthi

NOV 8 1985  
11-08-1985  
CONSERVATION DIVISION  
Wichita, Kansas