

To: 1 071016
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285
Operator: The Dane G. Hansen Trust
Name
Address P.O. Box 187
Logan, KS 67646

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated _____

Plugging Contractor The Dane G. Hansen Trust License Number 5285
Address P.O. Box 187, Logan, KS 67646

Company to plug at: Hour: 11 a.m. Day: 22 Month: 1 Year: 19 92

Plugging proposal received from Richard Wallgren
(company name) The Dane G. Hansen Trust (phone) 913-689-4816

were: 4 1/2" at 4480' w/175 sx cement, PBTD 4200', Perfs at 4105-09'
1st plug pump 500 lbs. hulls and 100 sx cement, displace down 4 1/2" to 4109',
2nd plug perforate at 1300' and pump 125 sx cement,
3rd plug pump 125 sx cement down backside.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 1992
01-28-1992
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 1:30 p.m. Day: 22 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 100 sx cement, displaced down
4 1/2" to 4109'.
2nd plug perforated at 1300', pumped down 4 1/2" with 125 sx cement. Maximum pressure 500 psi
and shut in 300 psi.
3rd plug pumped 125 sx cement down backside. Maximum pressure 500 psi and shut in 0 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOLVED (if necessary) observe this plugging.

DATE JAN 23 1992
INV. NO. 34401

Signed Dan Goodrow (TECHNICIAN)