

To: 1 060154 12-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,640-00-00/20
S/2 SE NE, SEC. 11, T. 16 S, R. 27 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6113
Operator: Landmark Oil Exploration, Inc.
Name & Address: 250 N. Water, Ste. 308
Wichita, KS 67202

2970 feet from S section line
660 feet from E section line
Lease Name Evel Well # 1-11
County Lane
Well Total Depth 4515 146.74 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 16 Month: 12 Year: 19 92

Plugging proposal received from Keith Van Pelt

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2014-50'
1st plug at 2075' with 50 sx cement, 2nd plug at 1300' with 50 sx cement,
3rd plug at 700' with 50 sx cement, 4th plug at 375' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 p.m. Day: 16 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2075' with 50 sx cement,
2nd plug at 1300' with 50 sx cement,
3rd plug at 700' with 50 sx cement,
4th plug at 375' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)
I did not observe this plugging.

DATE 1-19-93
NO. 37218

Signed Case Morris (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1992

