

To: 1071134 12-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,628 0000 117R  
NW NE SW, SEC. 9, T 16 S, R 27 W/E  
2310 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Lang Well # 1

Operator: Viking Resources, Inc.

County Lane

Name:

Address 105 S. Broadway, Ste. 1040

Well Total Depth 4597 149.40 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Viking Resources, Inc. License Number 5011

Address 105 S. Broadway, Ste. 1040, Wichita, KS 67202

Company to plug at: Hour: 4:10 p.m. Day: 18 Month: 12 Year: 19 92

Plugging proposal received from Terry Richardson

(company name) Viking Resources, Inc. (phone) 913-625-4567

Work: 4 1/2" at 4593' w/100 sx cement, Perfs at 4447-50'

1st plug pump 250 lbs. hulls and 100 sx cement on bottom,

2nd plug pump 50 sx cement at 2000' down casing,

3rd plug pump 80 sx cement at 1300',

4th plug pump 40 sx cement at 230', 5th plug top off with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8 p.m. Day: 18 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 250 lbs. hulls and 100 sx cement on bottom,

2nd plug pumped 50 sx cement at 2000' down casing,

3rd plug pumped 80 sx cement at 1300',

4th plug pumped 40 sx cement at 230',

5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered 2100' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE: 1-19-93

WELL NO: 37217 FEB 24 1993

12-18