

STATE

15-035-01152-0000

9

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Cowley County, Sec. 1 Twp. 33S Rge. 5 (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NW  
Lease Owner Catt Drilling Co., Inc.  
Lease Name Grose Well No. 1  
Office Address Box 427, Augusta, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8/18/64 19  
Application for plugging filed 8/18/64 19  
Application for plugging approved 8/18/64 19  
Plugging commenced 8/18/64 19  
Plugging completed 8/18/64 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess  
Producing formation Depth to top Bottom Total Depth of Well 3040' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8518	140	0 2-14-2012

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 203', 1/2 sack hulls, set plug and 15 sacks cement  
Mud to 40', 1/2 sack hulls, set plug and 8 sacks cement  
2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Catt Drilling Co., Inc.  
Address Box 427, Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
George W. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 31st day of August, 1964

[Signature]  
Billie Sanders

Notary Public.

My commission expires November 18, 1966

15035-01152-0000

R

Gatt Drilling Co., Inc.  
Grose # 1  
NE NE NW Sec. 1-33S-5E  
Cowley County, Kansas

WELL LOG

Commenced 8/11/64  
Completed 8/18/64  
R.T.D. 3040'

Set 140' of 8 5/8" Surface Casing

0-----	75	12 1/4 Hole
75-----	140	12 3/4 Surface hole
140-----	1070	Lime and Shale
1070-----	1400	Lime and Shale
1400-----	1615	Shale and Lime
1615-----	1784	Lime with Shale
1784-----	1806	Sand
1806-----	2001	Lime
2001-----	2194	Lime
2194-----	2236	Sand
2236-----	2356	Lime
2356-----	2383	Sand
2383-----	2679	Lime
2679-----	2745	Shale
2745-----	2846	Sand
2846-----	2930	Sand
2930-----	3005	Chert
3005-----	3040	Lime
3040-----		R.T.D.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1964

CONSERVATION DIVISION  
Wichita, Kansas