


15095-30016-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec 20 Twp. 29 Rge. (E) 6 (W)
Location as "NE/CNWxSWx" or footage from lines C SW NW
Lease Owner Pickrell Drilling Company
Lease Name Albright "E" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 26, 19 65
Application for plugging filed April 26, 19 65
Application for plugging approved April 26, 19 65
Plugging commenced April 26, 19 65
Plugging completed April 26, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4218 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 215'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th Natl Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th Natl Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1965

My commission expires June 21, 1966
Maxine Blackman, Notary Public.

ROTARY DRILLING LOG

15095-30016-000

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 4-14-65

Rotary Drilling Completed 4-26-65

LOCATION: ALBRIGHT "E" No. 1, C SW NW Section 20-29-6W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" surface casing set at 261' cemented with 165 sacks cement. Circulated. Completed 3:30 P.M. April 14, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Sand	
203	Red Bed	<u>C. F. S.</u> 3320
950	Shale & Shells	3335
1315	Shells & Lime	3687
1525	Lime & Shale	3709
1780	Lime	3733
2890	Lime & Shale	3775
2940	Lime	4125
3090	Lime & Shale	4135
3220	Lime, Shale & Sand	4145
3305	Lime & Shale	4152
3700	Lime	4159
3735	K. C.	4167
3775	Lime	4175
3910	Shale & Lime	4218
3963	Lime	
4159	Lime & Shale	<u>Slope Tests</u> 2500
4218	Mississippi & RTD	3000
		3500
		4000
		<u>S. L. M.</u> 3305
		3882
		4097

RECORDED
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 30th day of April, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public